

## 17271 Rising Dale Way, Ramona CA 92065 Ph # 619-733-7687

David & Jackie Swantner 1426 Barnett Rd, Ramona CA 92065 March 3, 2021 Proposal #030301

# PROPOSAL FOR VINYL PLANK FLOORING AREAS: BEDROOM #2/CLOSET, BEDROOM #3/CLOSET, HALL, COAT CLOSET, LIVING ROOM, ENTRY DINING ROOM, KITCHEN

#### **DEMO**

- Remove existing base and laminate flooring Haul away
- Move furniture, furniture only.
  - \*Home owner to remove all décor and delicate items, electronics, contents of furniture, etc

# **INSTALLATION**

- Install 1079 sq ft Floating vinyl plank flooring
- Install 36 I/ft Transition molding
- Caulk gap at top of molding around fireplace

### BASE

- Supply and install 272 l/ft MDF base up to 4", painted white
- Supply and install 46 l/ft ½ x ¾ base shoe at cabinets

TOTAL \$ 5,727.55	5
-------------------	---

### LEVELING ALLOWANCE

For budget purposes, average cost per wood sub floor

TOTAL ......\$ 1,436.00

### MATERIAL ALLOWANCE

- For Budget purposes, average cost for midgrade vinyl plank flooring
- Flooring 1187 sq ft
- Trims 8 pcs

TOTAL ...... \$ 4,177.75

#### OPTION #1 - SEALER

Supply and install Bona R540 warranted to 18 lbs on moisture test
 \*Will assess once laminate is removed

OPTION #1 TOTAL ...... \$ 751.60

### NOTES:

- Labor price is based on straight installation, installation on a diagonal or any other pattern is an additional charge.
- Climate must be controlled for wood flooring to perform properly. Temperature must be a consistent 65-85 degrees with a humidity level of 35-55%. Failure to do so may create issues with your flooring.
- Proposal does not include any paint or touch up painting to walls and/or base
- Proposal expires 4/3/2021